

Sub Subdivision of Township 3 North Range 35 East.

Chains	
38.70	<p>Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S, on N. face.</p> <p>Deposited charred stake 12 ins. in the ground for 1/16</p> <p>Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it. And in E pit drove stake 2 ft. long 2 ins. sq. 12 ins. in the ground marked 1/16 S. on N. face.</p>
58.05	<p>Deposited charred stake 12 ins. in the ground for 1/16</p> <p>Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it. And in E pit drove stake 2 ft. long 2 ins. sq. 12 ins. in the ground marked 1/16 S. on N. face.</p>
77.40	<p>To point of beginning.</p> <p>Land level.</p> <p>Soil 1st rate.</p>
<p>East on random through Center of Sec. 15.</p> <p style="text-align: right;">Va. 22° East.</p>	
77.22	<p>Commencing at ¼ Sec. cor. bet. Secs. 15 & 16..</p> <p>Set temporary cors. at 20, 40 and 60 chains. And at</p> <p>Intersect E. bdy. 35 lks. S. of ¼ Sec. cor. Thence</p> <p>S. 89° 45' West on true line.</p>
6.50	<p>Head of draw and spring.</p>
19.30	<p>Deposited charred stake 12 ins. in the ground for 1/16</p> <p>Sec. cor. Dug pits 18x18x12 ins. in E. & W. of stake 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.</p>
38.61	<p>Deposited charred stake 12 ins. in the ground for ¼ Sec. cor. Dug pits 18x18x12 ins. in E. & W. of stake 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked ¼ S. on N. face.</p>