

Subdivision of Township 3 North Range 35 East.

Chains. 19.32	Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it. And in E pit drove stake 2 ft. long 2 ins. sq. 12 ins. in the ground, marked 1/16 S. on N. face.	
38.64	Deposited charred stake 12 ins. in the ground for ¼ Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked ¼ S. on N. face.	
57.85	Gulch North.	-20
57.96	Set basalt stone 11x8x7 ins. 8 ins. in the ground for 1/16 Sec. cor. marked 1/16 on N. face. And raised mound of stone 1½ ft. high 3½ ft. base over it.	
77.30	To Cor. of beginning. Land rolling. Soil 1st rate.	
	Sept. 27, 1887.	
	East on random through N. ½ of Sec. 10. Va. 21° East. Commencing at 1/16 Sec. cor. 20 chains N. of ¼ Sec. cor. bet. Secs. 9 & 10. Set temporary cors. at 20, 40 and 60 chains. And at	
77.60	Intersect E. bdy. 44 lks. S. of 1/16 Sec. cor. Thence S. 89° 41' W. on true line.	
4.75	Canon N.	-50
9.00	Summit	\$100
11.50	Canon N.	-100
19.40	Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.	
38.80	Deposited charred stake 12 ins. in the ground for 1/16	