

## Sub Subdivision of Township 3 North Range 35 East.

Chains.	Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground, marked 1/16 S. on N. face.
57.90	Wagon road N. & S.
58.20	Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.
74.50	Gulch & spring branch 2 lks. wide bears N. W.
77.60	To corner of beginning. Land rolling. Soil fine. Not cultivated.

East on random through Center of Sec. 33.

Va. 22° East.

Commencing at ¼ Sec. cor. Bet. Secs. 32 & 33.

Set temporary cors. at 20, 40 and 60 chains. And at

80.10 Intersect E. bdy. 36 lks. S. of ¼ Sec. cor. Thence S. 89° 45' West. on true line.

20.02 Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face

40.05 Set basalt stone 15x10x8 ins. 10 ins. in the ground for ¼ Sec. cor. marked ¼ S. on N. face. And dug pits 18x18x12 ins. E. & W. of stake 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it.

60.08 Set basalt stone 12x9x8 ins. 8 ins. in the ground for 1/16 Sec. cor. marked 1/16 on N. face. Dug pits 18x18x12 ins. E. & W. of stone 5½ ft. dist. and raised mound of earth 1½ ft. high 3½ ft. base over it.