

## Sub Subdivision of Township 3 North Range 35 East.

Chains	
40.00	<p>And in E. pit drove stake 2 ft. long 2 ins. square 12 ins in the ground marked 1/16 S. on N. face.</p> <p>Deposited charred stake 12 ins. in the ground for <math>\frac{1}{4}</math> Sec. cor. Dug pits 18x18x12 ins. E. &amp; W. of stake <math>5\frac{1}{2}</math> ft. dist. raised mound of earth <math>1\frac{1}{2}</math> ft. high <math>3\frac{1}{2}</math> ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked <math>\frac{1}{4}</math> S. on N. face.</p>
60.00	<p>Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. &amp; W. of stake <math>5\frac{1}{2}</math> ft. dist. raised mound of earth <math>1\frac{1}{2}</math> ft. high <math>3\frac{1}{2}</math> ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.</p>
80.00	<p>To point of beginning.</p> <p>Land mostly level.</p> <p>Soil fine.</p> <p>Not cultivated.</p>
<p>East on random through N. <math>\frac{1}{2}</math> of Sec. 28.</p>	
<p style="text-align: right;">Va. <math>20\frac{1}{2}</math> East.</p>	
80.00	<p>Commencing at 1/16 Sec. cor. 20 chains N. of <math>\frac{1}{4}</math> Sec. cor. bet. Secs. 28 &amp; 29.</p> <p>Set temporary cors. at 20, 40 and 60 chains. And at Intersect E. bdy. 50 lks. S. of 1/16 Sec. cor. Thence S. <math>89^{\circ} 39'</math> W. on true line.</p>
20.00	<p>Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. &amp; W. of stake <math>5\frac{1}{2}</math> ft. dist. raised mound of earth <math>1\frac{1}{2}</math> ft. high <math>3\frac{1}{2}</math> ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.</p>
40.00	<p>Set basalt stone 9x8x7 ins. 6 ins. in the ground for 1/16 Sec. cor. marked 1/16 S. on N. face Dug pits 18x18x12 ins. E &amp; W. of stone <math>5\frac{1}{2}</math> ft. dist. raised mound of earth <math>1\frac{1}{2}</math> ft. high <math>3\frac{1}{2}</math> ft. base over it.</p>
45.00	<p>Gulch bears N. W.</p>
60.00	<p>Deposited charred stake 12 ins. in the ground for 1/16</p>