

Sub Subdivision of Township 3 North Range 35 East.

Chains	<p>East on random through Center of Sec. 21.</p> <p style="text-align: right;">Va. 20° East.</p> <p>Commencing at $\frac{1}{4}$ Sec. cor. bet. Secs. 20 & 21.</p> <p>Set temporary cors. at 20, 40 and 60 chains And at</p> <p>80.12 Intersect E. bdy. 35 lks. S. of $\frac{1}{4}$ Sec. cor. Thence S. 89° 45' W. on true line.</p> <p>20.00 Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5$\frac{1}{2}$ ft. dist. raised mound of earth 1$\frac{1}{2}$ ft. high 3$\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.</p> <p>40.06 Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ Sec. Cor. Dug pits 18x18x12 ins. E. & W. of stake 5$\frac{1}{2}$ ft. dist. and raised mound of earth 1$\frac{1}{2}$ ft. high 3$\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked $\frac{1}{4}$ S. on N. face.</p> <p>60.09 Set basalt stone 10x8x8 ins. 6 ins. in the ground for 1/16 Sec. cor. marked 1/16 on N. face. Dug pits 18x18x12 ins. E & W. of stone 5$\frac{1}{2}$ ft. dist. raised mound of earth 1$\frac{1}{2}$ ft. high 3$\frac{1}{2}$ ft. base over it.</p> <p>80.12 To point of beginning. Sand rolling, Soil 1st rate. Not cultivated.</p> <hr/> <p>East on random through N. $\frac{1}{2}$ of Sec. 21.</p> <p style="text-align: right;">Va. 20$\frac{3}{4}$° East.</p> <p>Commencing at 1/16 Sec. cor. 20 chains N. of $\frac{1}{4}$ Sec. cor. bet Secs. 20 & 21.</p> <p>Set temporary cors. at 20, 40 and 60 chains. And at</p> <p>80.20 Intersect E. bdy. 30 lks. S. of 1/16 Sec. cor. Thence S. 89° 47' West on true line.</p> <p>20.05 Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5$\frac{1}{2}$ ft. dist. raised mound of earth 1$\frac{1}{2}$ ft. high 3$\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.</p>
--------	---