

100

Sub Subdivisions of Township 3 North Range 35 East.

Chains	<p>of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base over it.</p> <p>80.16 To point of beginning.</p> <p>Land rolling.</p> <p>Soil 1st rate.</p>
	<p>East on random through center of Sec. 16.</p> <p style="text-align: right;">Va. 20° East.</p> <p>Commencing at $\frac{1}{4}$ Sec. cor, bet. Secs. 16 & 17.</p> <p>Set temporary cors. at 20, 40 and 60 chains. And at</p>
80.10	<p>Intersect E. bdy. 25 lks. S. of $\frac{1}{4}$ Sec. cor. Thence</p> <p>S $89^{\circ} 49'$ West on true line.</p>
20.02	<p>Deposited charred stake 12 ins. in the ground for 1/16</p> <p>Sec. cor. Dug pits 18x18x12 ins. E. and W. of stake $5\frac{1}{2}$</p> <p>ft. dist. raised mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base</p> <p>over it. And in E. pit drove stake 2 ft. long 2 ins.</p> <p>square 12 ins. in the ground marked 1/16 S. on N. face.</p>
40.05	<p>Set post 3 ft. long 3 ins. square 12 ins. in the ground</p> <p>for $\frac{1}{4}$ Sec. cor. marked $\frac{1}{4}$ S. on N. face. Dug pits 18x18x</p> <p>12 ins. E. & W. of stake $5\frac{1}{2}$ ft. dist. raised mound of</p> <p>earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base around post.</p>
60.08	<p>Set basalt stone 10x8x7 ins. 6 ins. in the ground for 1/16</p> <p>Sec. cor. marked 1/16 on N. face. Dug pits 18x18x12 ins.</p> <p>E. & W. of stone $5\frac{1}{2}$ ft. dist. raised mound of earth $1\frac{1}{2}$ ft.</p> <p>high $3\frac{1}{2}$ ft. base over it.</p>
80.10	<p>To point of beginning.</p> <p>Land mostly rolling.</p> <p>Soil 1st rate.</p> <p>Good grass.</p>
	<p>East on random through N. $\frac{1}{2}$ of Sec. 16</p> <p style="text-align: right;">Va. $20\frac{1}{2}^{\circ}$ East.</p> <p>Beginning at 1/16 Sec. cor. 20 chains S. of N.W. cor. of</p> <p>Sec. 16. Set temporary cors. at 20, 40 and 60 chains. And</p> <p>at</p>
80.00	<p>Intersect E. bdy. 35 lks. S. of $\frac{1}{16}$ Sec. cor. Thence</p>