

Sub Subdivision of Township 3 North Range 35 East.

Chains	<p>Sec. cor. Dug pits 18x18x12 ins. E. &amp; W. of stake 5½ft.                      dist.raised mound of earth 1½ ft. high 3½ ft. base                      over it. And in E. pit drove stake 2 ft. long 2ins. sq.                      12 ins. in the ground marked 1/16 S. on N. face.</p>
43.00	Fence and leave field.
59.92	<p>Deposited charred stake 12 ins. in the ground for 1/16                      Sec. cor. Dug pits 18x18x12 ins. E. &amp; W. of stake 5½ft.                      dist. raised mound of earth 1½ ft. high 3½ ft. base                      over it. And in E pit drove stake 2 ft. long 2 ins. sq.                      12 ins. in the ground marked 1/16 S. on N. face.</p>
79.90	<p>To point of beginning.                      Land level.                      Soil 1st rate.</p>
<p>East on random through center of sec. 9.  <span style="float: right;">Va. 20° East.</span></p>	
79.80	<p>Commencing at ¼ Sec. cor. bet. Secs. 8 &amp; 9.                      Set temporary cors. at 20, 40 and 60 chains. And at                      Intersect E. bdy. 40 lks. S. of ¼ Sec. cor. Thence                      S 89° 43' W. on true line.</p>
19.95	<p>Deposited charred stake 12 ins. in the ground for 1/16                      Sec. cor. Dug pits 18x18x12 ins. E. &amp; W. of stake 5½                      ft. dist. raised mound of earth 1½ ft. high 3½ ft.                      base over it. And in E. pit drove stake 2 ft. long 2                      ins. square 12 ins. in the ground marked 1/16 S. on                      N. face.</p>
20.95	Gulch North
39.90	<p>Deposited charred stake 12 ins. in the ground for ¼ Sec.                      cor. Dug pits 18x18x12 ins. E. &amp; W. of stake 5½ ft.                      dist. raised mound of earth 1½ ft. high 3½ ft. base                      over it. And in E. pit drove stake 2 ft. long 2ins.                      square 12 ins. in the ground marked ¼ S. on N.face.</p>
59.85	<p>Deposited charred stake 12 ins. in the ground for 1/16                      Sec.cor. Dug pits 18x18x12 ins. E. &amp; W. of stake 5½                      ft. dist. raised mound of earth 1½ ft. high 3½ ft. base                      over it. And in E pit drove stake 2 ft. long 2 ins.</p>