

SubSubdivision of Township 3 North Range 35 East.

Chains.	N. face.
40.02	Deposited charred stake 12 ins, in the ground for $\frac{1}{4}$ Sec. cor, Dug pits 18x18x12 ins. E. & W. of stake 5 $\frac{1}{2}$ ft. dist. raised mound of earth 1 $\frac{1}{2}$ ft. high 3 $\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked $\frac{1}{4}$ S, on N. face.
53.50	Fence N. & S.
60.03	Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5 $\frac{1}{2}$ ft. dist. raised mound of earth 1 $\frac{1}{2}$ ft. high 3 $\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.
80.04	To point of beginning. Land level, soil good. Not cultivated.
<hr/> East on random through N. $\frac{1}{2}$ of Sec 29. Va. 20 $\frac{1}{2}$ ° East Began at 1/16 Sec. cor. 20 chains N. of $\frac{1}{4}$ Sec. cor. bet. Secs. 29 & 30.	
80.00	Set temporary cors at 20, 40 and 60 chains. And at Intersect E. bdy. 15 lks. S. of 1/16 Sec. cor. Thence S. 89° 54' W. on true line.
20.00	Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5 $\frac{1}{2}$ ft. dist. raised mound of earth 1 $\frac{1}{2}$ ft. high 3 $\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.
40.00	Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5 $\frac{1}{2}$ ft. dist. raised mound of earth 1 $\frac{1}{2}$ ft high 3 $\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2ft. long 2 ins. sq. 12 ins. in the ground marked 1/16 S. on N. face.
53.50	Cross fence course N. & S.