

Sub Subdivision of Township 3 North Range 35 East.

Chains 60.00	Set basalt stone 14x8x5 ins. 10 ins. in the ground for 1/16 Sec. cor. marked 1/16 on N. face. Dug pits 18x18x12 ins. E. & W. of stone 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.
80.00	To point of beginning. Land rolling. Soil 1st rate.
East on random through S. ½ of Sec. 20. Va. 20° East.	
Commencing at 1/16 Sec. cor. 20 chains North of S. W. cor. of Sec. 20.	
80.00	Set temporary cors. at 20, 40 and 60 chains. And at Intersect E. bdy. 12 lks. S. of 1/16 Sec. cor. Thence S. 89° 55' W. on true line.
20.00	Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.
40.00	Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.
60.00	Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.
80.00	To point of beginning. Land rolling. Soil 1st rate.