

Sub Subdivision of Township 3 North Range 35 East

Chains	
40.04	<p>over it. And in E. pit drove stake 2 ft. long 2 ins. sq. 12 ins. in the ground marked 1/16 S. on N. face.</p> <p>Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. dug pits 18x18x12 ins. E. &amp; W. of stake 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.</p>
60.06	<p>Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. &amp; W. of stake 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.</p>
80.08	<p>To point of beginning.</p> <p>Land. slightly rolling.</p> <p>Soil 1st rate.</p> <p>Partly cultivated.</p>
<p>East on random through Center of Sec. 8.</p> <p style="text-align: right;">Va. 20° East.</p>	
80.14	<p>Began at ¼ Sec. cor. bet. Secs. 7 &amp; 8.</p> <p>Set temporary cors. at 20, 40 and 60 chains. And at Intersect E. bdy. 15 lks. S. of ¼ Sec. cor. Thence S. 89° 54' West on true line.</p>
20.04	<p>Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. &amp; W. of stake 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.</p>
40.00	<p>H. Vaughn's House bears N. 8 chains.</p>
40.07	<p>Deposited charred stake 12 ins. in the ground for ¼ Sec. Cor. Dug pits 18x18x12 ins. E. &amp; W. of stake 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked ¼ S. on N. face.</p>
60.10	<p>Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. &amp; W. of stake 5½</p>