

Sub Subdivision of Township 3 North Range 35 East.

Chains	
40.06	<p>dist. raised mound of earth $1\frac{1}{2}$ ft, high $3\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked $\frac{1}{16}$ S. on N. face.</p> <p>Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake $5\frac{1}{2}$ ft. dist. raised mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked $\frac{1}{4}$ S. on N. face.</p>
60.09	<p>Deposited charred stake 12 ins. in the ground for $\frac{1}{16}$ Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake $5\frac{1}{2}$ ft. dist. raised mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked $\frac{1}{16}$ S. on N. face.</p>
80.12	<p>To point of beginning.</p> <p>Land level or mostly so.</p> <p>Soil 1st rate.</p> <p>All cultivated.</p>
80.00	<p>East on random through N. $\frac{1}{2}$ of Sec. 5.</p> <p style="text-align: right;">Va. 20° East.</p> <p>Began at $\frac{1}{16}$ Sec. cor. 20 chains N. of $\frac{1}{4}$ Sec. cor. bet. Sec. 5 & 6.</p> <p>Set temporary Cors. at 20, 40 and 60 chains. And at Intersect E. bdy 25 lks. S. of $\frac{1}{16}$ Sec. cor. Thence S. $89^{\circ} 49'$ W. on true line.</p>
20.00	<p>Set post 3 ft. long 3 ins. square 24 ins. in the ground for $\frac{1}{16}$ Sec. cor. marked $\frac{1}{16}$ S. on N. face. Dug pits 18x18x12 ins. E. & W. of post. $5\frac{1}{2}$ ft. dist. raised mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base around post.</p>
40.00	<p>Set post 3 ft. long 3 ins. square 24 ins. in the ground for $\frac{1}{16}$ Sec. cor. marked $\frac{1}{16}$ S. on N. face. Dug pits 18x18x12 ins. E. & W. of stake $5\frac{1}{2}$ ft. dist. and raised mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base around post.</p>
60.00	<p>Set post 3 ft. long 3 ins. square 24 ins. in the ground for $\frac{1}{16}$ Sec. cor. marked $\frac{1}{16}$ S. on N. face. Dug pits 18x18x12 ins. E. & W. of stake $5\frac{1}{2}$ ft. dist. and raised</p>