

111

Sub Subdivision of Township 3 North Range 35 East.

Chains.	
	<p>West on random through N. $\frac{1}{2}$ of Sec. 31</p> <p style="text-align: right;">Va. 21° East.</p> <p>Began at 1/16 Sec. cor. 20 chains N. of $\frac{1}{2}$ Sec. cor. bet. Sec. 31 & 32.</p> <p>Set temporary Cor. at 20, 40 and 60 chains. And at</p>
77.32	<p>Intersect W. bdy. 12 lks. N. of 1/16 Sec. cor. Thence N. 89° 55' E. on true line.</p>
17.32	<p>Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5$\frac{1}{2}$ ft. dist. raised mound of earth 1$\frac{1}{2}$ ft. high 3$\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.</p>
37.32	<p>Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5$\frac{1}{2}$ ft. dist. raised mound of earth 1$\frac{1}{2}$ ft. high 3$\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.</p>
57.32	<p>Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5$\frac{1}{2}$ ft. dist. raised mound of earth 1$\frac{1}{2}$ ft. high 3$\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.</p>
77.32	<p>To point of beginning.</p> <p>Land, level. Soil 1st rate.</p> <p>Not cultivated.</p>
	<p>West on random through S. $\frac{1}{2}$ of Sec. 30.</p> <p style="text-align: right;">Va. 21° East.</p> <p>Began at 1/16 Sec. cor. 20 chains N. of S. E. cor. of Sec. 30.</p>
77.08	<p>Set temporary cors. at 20, 40 and 60 chains. And at Intersect W. bdy. 12 lks. N. of 1/16 Sec. cor. Thence N. 89° 55' E. on true line.</p>
17.08	<p>Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5$\frac{1}{2}$ ft. dist. raised mound of earth 1$\frac{1}{2}$ ft. high 3$\frac{1}{2}$ ft. base</p>