

## Sub Subdivision of Township 3 North Range 35 East.

Chains 57.12	Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5½-ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.
77.12	To point of beginning. Land level, Soil 1st rate. Not cultivated.
	West on random through N. ½ of Sec. 30. Va. 21° East. Began at 1/16 Sec. cor. 20 chains N. of ¼ cor. bet. Secs. 29 & 30. Set temporary cor. at 20, 40 and 60 chains. And at
77.18	Intersect W. bdy. 30 lks. N. of 1/16 Sec. cor. Thence N. 89- 47½ East on true line.
17.18	Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.
37.18	Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. dug pits 18x18x12 ins. E. & W. of stake 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.
57.18	Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.
77.18	To point of beginning. Land rolling. Partly cultivated.