

Sub Subdivision of Township 3 North Range 35 East

| Chains | |
|--------|--|
| | ft. dist. raised mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face. |
| 37.20 | Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake $5\frac{1}{2}$ ft. dist. raised mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked $\frac{1}{4}$ S. on N. face. |
| 57.20 | Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake $5\frac{1}{2}$ ft. dist. raised mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face. |
| 77.20 | To point of beginning. Land level. Soil 1st class. Mostly cultivated. |
| | West on random through N. $\frac{1}{2}$ of Sec. 19. Va. $19\frac{3}{4}^{\circ}$ East. |
| | Began at 1/16 Sec. cor. 20 chains N. of $\frac{1}{4}$ Sec. cor. bet. Secs. 19 & 20. |
| 77.18 | Set temporary cors. at 20, 40 and 60 chains. And at Intersect W. bdy. 14 lks. N. of 1/16 Sec. cor. Thence N. $89^{\circ} 54'$ E. on true line. |
| 17.18 | Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake $5\frac{1}{2}$ ft. dist. raised mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face. |
| 37.18 | Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake $5\frac{1}{2}$ ft. dist. raised mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face. |
| 57.18 | Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake $5\frac{1}{2}$ ft. dist. raised mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base over |