

Sub Subdivision of Township 3 North Range 35 East.

	<p>it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.</p>
77.18	<p>To point of beginning.</p> <p>Land level. Soil 1st rate. All cultivated.</p>
	<p>West on random through S. $\frac{1}{2}$ of Sec. 18. Va. 20° East.</p>
	<p>Began at 1/16 Sec. cor. 20 chains N. of S. E. cor. of Sec. 18.</p>
	<p>Set temporary corm. at 20, 40 and 60 chains. And at</p>
77.23	<p>Intersect West bdy. 14 lks. N. of 1/16 Sec. cor. Thence N., 89° 54' E. on true line.</p>
2.00	<p>Lane and wagon road N. & S. And enter field.</p>
17.23	<p>Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5$\frac{1}{2}$ ft. dist raised mound of earth 1$\frac{1}{2}$ ft. high 3$\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.</p>
37.23	<p>Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5$\frac{1}{2}$ ft. dist. raised mound of earth 1$\frac{1}{2}$ ft. high 3$\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.</p>
57.23	<p>Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5$\frac{1}{2}$ ft. dist. raised mound of earth 1$\frac{1}{2}$ ft. high 3$\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. sq. 12 ins. in the ground marked 1/16 S. on N. face.</p>
77.23	<p>To point of beginning</p> <p>Land mostly level</p> <p>Soil good.</p>