

## Sub Subdivision of Township 3 North Range 35 East.

Chains	
57.42	<p>on N. face.</p> <p>Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. &amp; W. of stake 5<math>\frac{1}{2}</math> ft. dist. raised mound of earth 1<math>\frac{1}{2}</math> ft. high 3<math>\frac{1}{2}</math> ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.</p>
77.42	<p>To point of beginning.</p> <p>Land level or mostly so.</p> <p>Soil 1st rate. All cultivated.</p>
	<p>West on random through Center of Sec 7.</p> <p style="text-align: right;">Va. 20° East.</p>
77.45	<p>Began at <math>\frac{1}{4}</math> Sec. cor. bet. 7 &amp; 8.</p> <p>Set temporary cors. at 20, 40 and 60 chains. And at Intersect W. bdy. 16 lks. N. of <math>\frac{1}{4}</math> Sec. cor. Thence North 89° 53' East on true line.</p>
.50	<p>Fence &amp; leave Wagon road N. &amp; S.</p>
17.45	<p>Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. &amp; W. of stake 5<math>\frac{1}{2}</math> ft. dist. raised mound of earth 1<math>\frac{1}{2}</math> ft. high 3<math>\frac{1}{2}</math> ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.</p>
22.00	<p>Branch runs N. W.</p>
37.45	<p>Deposited charred stake 12 ins. in the ground for <math>\frac{1}{4}</math> Sec. cor. Dug pits 18x18x12 ins. E. &amp; W. of stake 5<math>\frac{1}{2}</math> ft. dist. raised mound of earth 1<math>\frac{1}{2}</math> ft. high 3<math>\frac{1}{2}</math> ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked <math>\frac{1}{4}</math> S. on N. face.</p>
57.45	<p>Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. &amp; W. of stake 5<math>\frac{1}{2}</math> ft. dist. raised mound of earth 1<math>\frac{1}{2}</math> ft. high 3<math>\frac{1}{2}</math> ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.</p>
77.45	<p>To point of beginning.</p> <p>Land rolling, soil fine.</p> <p>Partly under cultivation.</p>