

## Subdivision of Township 3 North Range 35 East.

Chains 37.28	Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake $5\frac{1}{2}$ ft. dist. raised mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2 ft. 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.
57.28	Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake $5\frac{1}{2}$ ft. dist. raised mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. sq. 12 ins. in the ground marked 1/16 S. on N. face.
77.28	To point of beginning. Land level. Soil 1st rate. Not cultivated.
West on random through N. $\frac{1}{2}$ of Sec. 6. Va. 20° East.	
Began at 1/16 Sec. cor. 20 chains N. of $\frac{1}{4}$ Sec. cor. bet Secs. 5 & 6. Set temporary 1/16 Sec. cors. at 20, 40 and 60 chains. And at	
77.24	Intersect W. bdy. 25 lks. N. of 1/16 Sec. cor. Thence N. 89° 49' East on true line.
17.24	Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake $5\frac{1}{2}$ ft. dist. raised mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.
37.24	Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake $5\frac{1}{2}$ ft. dist. raised mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. sq. 12 ins. in the ground marked 1/16 S. on N. face.
57.24	Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake $5\frac{1}{2}$ ft. dist. raised mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base