

Sub Subdivision of Township 3 North Range 35 East.

Chains

77.24

over it. And in E. pit drove stake 2 ft. long 2 ins. sq.  
 . 12 ins. in the ground marked 1/16 S. on N. face.

To point of beginning.

Land rolling.

Soil 1st rate.

Not cultivated.

Oct. 4th. 1887.

Field Notes

Examination of Corners Exterior Lines of Township 3 North  
 Range 34 East, Willamette Meridan, Oregon as surveyed by  
 James P. Currin & James E. Noland U.S. Deputy Surveyor,  
 under special contract dated May 4th, 1887.

Survey commenced, April 26th. 1890.

Survey completed, May 1st. 1890.

Find cor. to T. 3 & 4 N. R. 34 & 35 E. To be a Pine post  
 48x6x8 ins. 24 ins. in the ground marked S. 31, T 4  
 N. R 35, E, on N.E. S 6 T 3 N R, 35, E on S. E. S 1 T.  
 3 N. R 34, E on S W., S 36 T 4 N R 34, E on N. W. faces.  
 With 6 notches on N.E. S & W. edges with pits 6 ft. dist.  
 on each line & earth mound around post.

South to cors. Secs 1, 6, 7, & 12, a stone 12x10x8 ins.  
 firmly set in ground with 1 notch on N. and 5 on S.  
 edges. Pits 5 1/2 ft. dist. in each Sec. mound around it.  
 Pits partly filled mounds scattered. South bet. Secs.  
 7 & 12. I find that cor Sec. 7, 12, 13 & 18 is plowed  
 up and gone.

Going south to the cor. to Secs. 19, 24, 13 & 18. I found  
 a post 4 ft. long by 2 ins. square firmly set in the  
 ground marked S. 18 T. 3 N. on N.E.S. 19 R. 35 E. on  
 S.E.S. 24 R. 34, E. on S. W. S 13 on N. W. faces with  
 3 notches on N. & S. edges. Mound & pits nearly de-  
 stroyed by plowing.

Corner to Secs. 19, 24, 25 & 30, a post 2 ft. long 4 ins.