

Subdivision of Township 3 North Range 35 East.

Chains

Found cor. Sec. 16, 17, 20 and 21. mound & pits plowed over & destroyed. The stake 3 ft. long by 3 ins. square was found lying on plowed ground marked S 16 T 3, N on N.E. S 21, R 35, E. on S E. S 20 on S W. & S 17 on N.W. faces, with 4 notches on E. & 3 on S. edges.

April 28, 1890

Survey for Topography Lines of Township 3 North Range 35 East, Willamette Meridian, Oregon, as surveyed by James P. Currin & James E. Noland. U.S. Deputy Surveyor, under their Special Contract, Dated May 4th, 1887.

Survey commenced April 25th. 1890

Survey completed May 1st. 1890.

Section 32

Retracing the lines through N. $\frac{1}{2}$ of Sec. 32. I found the corner about all destroyed by fencing and plowing and was therefore unable to locate the old road

Bet Secs. 28 and 29. Beginning at cors Secs. 28 and 29, 32 & 33, which is a stone 9x8x7 marked with 4 notches on E. & one on S. edges. Mound most gone & pits obliterated by the plow. I ran north bet. Sec. 28 & 29 but all trace of road is gone.

Section 27

Center line plowed up & road obliterated.

Section 23

From cor. Secs. 22, 23, 26 & 27, a stone 9x8x7 ins. with 2 notches S. & 2 on E. edges. I ran

N. 89° 31' E. Tracing line bet. Sec. 23 & 26

Va. 20° E.

19.90

Found 1/16 Sec. cor. a stone in stone mound. Stone marked 1/16.

24.60

Road freshly traveled.

Went on to $\frac{1}{4}$ Sec. cor. & to brink of canyon & could find no other road.

From 1/16 Cor. 20 chains N. of S.W. cor. of Sec. 23.