

Retracement-Resurvey Subdivisions, T. 3 N., R. 35 E.

Chains
79.94

Intersect the cor. of secs. 26, 27, 34 and 35, which is a 2-inch iron post, firmly set extending 10 inches above ground, with brass cap marked

T3N	R35E
S27	S26
S34	S35
1919	

This cor. stands in line of fence, bearing N. and S., and dividing grain fields.

Land, level, rolling and mountainous.

Soil, rich mellow loam, 1st rate and rocky, 4th rate.

Timber, scattering balm.

Undergrowth, thorn, briars and vine.

-Retracement

From the cor. of secs. 33 and 34 on the S. bdy. of the Tp. N. 0° 52' W., refracting the line bet. secs. 33 and 34; at 39.45 chs. find no trace of the 1/4 sec. cor. set temp. cor. thence I continue my retracement North, and at 60.38 chs. fall 60 lks. W. of the 1/16 sec. cor., and at 80.66 chs. fall 18 lks. W. of the cor. of secs. 27, 28, 33 and 34.

From the cor. of secs. 33 and 34 on the S. bdy. of the Tp. North, resurveying the line bet. secs. 33 and 34.

Over open rocky S. slope ascend 525 ft.

32.40 Top of ascent; fence, bears E. and W., enter grain field on gently rolling land.

40.07 Apportioned distance.

Set iron post, 3 ft. long 1 in. diam., 27 ins. in the ground, for 1/4 sec. cor., with brass cap marked.

S33	S34
1923	

Cor. stands in open wheat field, pits mound or other accessories impracticable.

60.38 Intersect the N. 1/16 sec. cor. of secs. 33 and 34, which is a 2-inch iron post, firmly set, extending 10 inches above the ground, with brass cap marked