

Retracement-Resurvey Subdivisions, T. 3 N., R. 35 E.

Chains.

T3N	R35E
N	1/16
S33	S34
1919	

This cor. stands at intersection of division fences which bears N., E. and W.

Thence

N. 1° 11' W., continuing my measurements.

Along fence between grain fields.

80.66 Intersect the cor. of secs. 27, 28, 33 and 34, which is a 2-inch iron post, firmly set, extending 10 inches above ground, with brass cap marked

T3N	R35E
S28	S27
S33	S34
1919	

No accessories practicable.

Land rolling and level.

Soil, rich mellow loam, 1st rate; rocky, 4th rate.

Timber none.

Undergrowth, none.

From the cor. of secs. 26, 27, 34 and 35.

West, retracing the line bet. secs. 27 and 34.

Over gently rolling land, through grain field.

23.70 Leave grain field, bears N. and S., descend W. slope, 235 ft.

25.20 Fence, bears N. and S., descend abruptly.

33.85 Spring branch, 2 lks. wide, in deep canyon, course S. ascend E. slope, 100 ft. to

39.25 Fall 38 lks. S. of the $\frac{1}{4}$ sec. cor., which is a 2-inch iron post, firmly set in a mound of stone, with brass cap marked.

T3N	R35E
$\frac{1}{4}$ S	27
S34	
1919	

The true course and length of this line is N. 89° 27' W., 39.25 chs.

From the $\frac{1}{4}$ sec. cor.