

Township 3 North, Range 36 East

Chains 40.00	<p>Set post corner for $\frac{1}{4}$ section, from which</p> <p>A larch, 4 in dia. bears S.84°E. 18 lks.</p> <p>A larch, 3 in dia. bears N.15°W. 13 lks.</p>
80.00	<p>Set post corner, sections 2, 3, 34 & 35, from which</p> <p>A fir, 20 in dia. bears N.2° E. 40 lks.</p> <p>A fir, 3 in dia. bears N.55°W. 29 lks.</p> <p>A fir, 3 in dia. bears S.57°W. 25 lks.</p> <p>A fir, 24 in dia. bears East 28 lks.</p> <p>This line passes through thick timber of small growth. Considerable down timber. Undergrowth thick. Timber, fir, larch and pine. Undergrowth, the same with willow.</p>
	<p>S.89°39'E. on North boundary of Section 2. Var. 19° East.</p>
40.00	<p>Set post corner for $\frac{1}{4}$ section, from which</p> <p>A larch, 12 in dia. bears N.60°W. 30 lks.</p> <p>A larch, 8 in dia. bears S.40°E. 38 lks.</p>
80.00	<p>Set post corner for Sections 1, 2, 35 & 36, from which</p> <p>A fir, 18 in dia. bears S.88°E. 39 lks.</p> <p>A fir, 6 in dia. bears N.10°E. 110 lks.</p> <p>A fir, 14 in dia. bears N.45°W. 60 lks.</p> <p>A fir, 12 in dia. bears West 40 lks.</p> <p>This line passes through thick timber, valuable to farmers, considerable dead and fallen undergrowth, thick, making it tedious, getting through. Timber, fir, larch and pine. Undergrowth, the same with willow.</p>
	<p>S.89°39'E. on North boundary of section 1. Var. 19°30'E.</p>
40.00	<p>Set post corner for $\frac{1}{4}$ section on hillside, facing the West, from which</p> <p>A fir, 10 in dia. bears N.80°W. 43 lks.</p> <p>A fir, 8 in dia. bears S.77°W. 50 lks.</p>
80.00	<p>To post corner</p> <p>This line passes along near the break of the hill toward</p>