

Subdivisional Lines of Township 3 North, Range 36 E. W. M.

Chains	Tamarack, 16 in diam. brs. N. 5° E. 17 lks. dist.	
	Tamarack, 12 in diam. brs. West 33 lks. dist.	
43.50	Spring branch, course NW. and leave timber NW. & SE.	-50
71.00	Top of ridge, course NW. & SE. Enter timber	+100
80.00	A fir, 5 in diam. on East side near top of ridge for corner to sections 25, 26, 35 and 36.	-80
	A fir, 8 in diam. brs. N. 50° E. 80 lks. dist.	
	A fir, 12 in diam. brs. S. 18° E. 140 lks. dist.	
	A fir, 10 in diam. brs. S. 61° W. 100 lks. dist.	
	Land; Surface, mountainous:	
	Soil, 3rd rate, part 2nd rate: Some good timber. Fir, tamarack and pine. Some willow and several other kinds of underbrush for which I do not know any name.	
	Good bunch grass on open ground.	
	September 28th 1878.	
	East on a random line between sections 25 and 36.	
	Va. 16°30' East.	
40.00	Set post for temporary $\frac{1}{4}$ sec. cor.	
79.84	Intersected East Boundary 8 lks. North of corner to sections 25 and 36, from which corner I run N. 89°57' West, on a true line between Sec. 25 and 36.	
	Va. 20° East.	
1.50	Top of ridge, course NW. & SE.	+10
28.00	Enter timber, NW. & SE.	-350
38.00	Top of ridge, NW. & SE. and leave timber	+250
39.92	Set stone 15x10x4 on SW. hillside for $\frac{1}{4}$ sec. cor. from which	
	A pine 20 in diam. brs. N. 27° E. 127 lks. dist.	
53.00	Ravine & spring branch NW. and enter timber NW. & SE.	-300
79.84	The corner to Sections 25, 26, 35 and 36.	+400
	Land: Surface, mountainous. Soil, 3rd and 2nd rate. Good timber on North and NE. hillsides. Fir, tamarack and pine. South and SW. hillsides open and good bunch grass.	
	Sec. 36 is mostly mountainous, the SE. $\frac{1}{4}$ is mostly near-	