

Subdivisional Lines of Township 3 North, Range 36 E. W. M.

Chains	ly level and is nearly all covered with good timber.	
	North between sections 25 and 26.	
	Va. 16°30' East.	
	Down along East side of ridge.	
40.00	Set stone 14x10x5 on steep East hillside for $\frac{1}{4}$ sec. cor.	-250
	from which	
	A pine, 8 in diam. brs. S. 36° E. 86 lks. dist.	
	A fir, 10 in diam. brs. S. 43° W. 100 lks. dist.	
80.00	Set stone 12x10x8 on steep East hillside for corner to	-350
	Sec. 23, 24, 25 and 26, from which	
	A fir, 8 in diam. brs. S.46°W. 68 lks. dist.	
	A pine, 20 in diam. brs. N.45°W. 148 lks. dist.	
	No other trees near in Sec. 24 & 25.	
	Land: Surface, mountainous: Soil, 3rd & 2nd rate: Timber	
	good in most of this mile. Fir, tamarack and pine,	
	some underbrush: good bunch grass in opening.	
	East on a random line between Sec. 24 and 25.	
	Va. 22°15' East.	
40.00	Set post for temporary $\frac{1}{4}$ sec. cor.	
80.25	Intersected E. Boundary 36 lks. North of cor. to Sec. 24	
	and 25 from which corner I run	
	N.89°45' West on a true line between Sec. 24 and 25.	
	Va. 20° East.	
12.00	Spring-branch & timber course North	-200
35.00	Top of ridge N. & S. leave timber	+350
40.13	Set stone 16x8x5 on West hillside in mound of stone for	-50
	$\frac{1}{4}$ sec. cor.	
59.00	Brook, 4 lks. wide, course North	-600
80.25	The cor. to Sec. 23, 24, 25 and 26.	+600
	Land: Surface, mountainous: Soil, 3rd & 2nd rate. Fir,	
	tamarack & pine: Willow and other underbrush: good	
	bunch grass in openings. About $\frac{1}{4}$ of Sec. 25 is co-	
	vered with timber, standing in groves on North and NE.	
	hillsides.	
	September 30th 1878	