

Subdivisional Lines of Township 3 North, Range 36 E. W. M.

Chains		
	North between Sec. 23 and 24. Va. 22°15' East.	
	Down along East side of ridge.	
40.00	Set fir post on East side of ridge for $\frac{1}{4}$ sec. cor. from which A fir, 8 in diam. brs. N.10°E. 52 lks. dist. A fir, 10 in diam. brs. N. 22° W. 60 lks. dist.	-650
49.50	Brook, 6 lks. wide, course NW.	-150
52.00	Clark Harrington's house brs. N.33°E.	
64.50	Umatilla River 80 lks. wide, co. West.	-80
66.50	Road, E. & W. leads from Pendleton to La Grand. C. H.'s house brs. East.	
71.00	Steep bluff, East & West.	
80.00	Set stone 15x10x7 on NE. side of spur for cor. to Sec. 13, 14, 23 and 24. Drove stake and raised mounds of stone around stake and stone in lieu of pits. Land: Surface, mountainous. Soil, 3rd & 2nd rate. Small part on river, 1st rate. Some good timber. Fir, pine and tamarack. Good bunch grass. Willows & other underbrush.	+200
	East on a random line between Sec. 13 and 24. Va. 18°45' East.	
40.00	Set post for temporary $\frac{1}{4}$ sec. cor.	
79.80	Intersected E. boundary 395 lks. North of post corner to Sec. 13 and 24 from which corner I run N.87°11' West on true line between sections 13 and 24.	
	Va. 20° East.	
5.50	Cross ridge to NW. side.	-40
37.00	River bottom NE. & SW.	-800
39.90	Set stone 12x10x10 for $\frac{1}{4}$ sec. cor. A fir, 30 in diam. brs. S. 5° E. 34 lks. dist. An alder, 4 in diam. brs. N.44°W. 24 lks. dist.	
51.00	Umatilla, 75 lks. wide, course NW.	
65.00	Steep bluff, NE. & SW.	
79.80	The cor. to Sec. 13, 14, 23 and 24.	+200