

Subdivisional Lines of Township 3 North, Range 36 E. W.M.

Chains	<p>North on a random line between Sec. 1 and 2. Va. 21° East.</p> <p>40.00 Set post for temporary $\frac{1}{4}$ sec. cor.</p> <p>75.25 Intersected North Boundary 78 lks. East of cor. to Sec. 1 and 2, from which cor. I run S.0°33' East on a true line between sections 1 and 2. Va. 19°30' East.</p> <p>35.25 A tamarack 4 in diam. for $\frac{1}{4}$ sec. cor., from which a Fir, 16 in diam. brs. N. 32° E. 17 lks. dist. Fir, 12 in diam. brs. S. 52° W. 26 lks. dist.</p> <p>75.25 The cor. to Sec. 1, 2, 11 and 12. Land: Surface, rolling. Soil, 2nd and 1st rate, mostly good timber; has been very much cut away in places. Tamarack, pine and fir: some Willow and other underbrush. Section 1 has some very good timber yet. Oct. 3rd 1878.</p> <hr/> <p>After diligent and careful search I can find no trace of corner to Sections 34 and 35. I therefore return to the corner of sections 35 and 36 and I run West along the South Boundary of Sec. 35. Va. 18°45' E.</p>	
37.50	Spring branch, course SW.	-450
58.00	Spring branch, course SW.	-100
71.00	Brook, 20 lks. wide, course NW. also enter timber	-100
80.00	Set stone 14x10x7 on North hillside for corner to Sec. 34, 35, 2 and 3, from which A fir, 12 in diam. brs. N.82° E. 164 lk. dist. A pine, 14 in diam. brs. S. 80°E. 167 lk. dist. A pine, 4 in diam. brs. S. 72°W. 21 lk. dist. No tree in Sec. 34	+80
	<p>North between Sec. 34 and 35. Va. 20° East.</p>	
6.00	Brook, 20 lks. wide, course NW.	-75
40.00	Set stone 16x12x 4 on South hillside for $\frac{1}{4}$ sec. cor.	+200

↑
X