

Subdivisional Lines of Township 3 North, Range 36 E. W. M.

Chains		
	<p>to Sec. 14, 15, 22 and 23. Drove stake and raised mound of stone around stone and stake in lieu of pits. Land: Surface, mountainous. Soil, 3rd rate, some, 1st rate on river bottom. Some good timber South of and in river bottom. Pine, fir, tamarack and balm; some willow and other underbrush. Good grass.</p> <p style="text-align: center;">Oct. 5th 1878.</p>	
	<p>East on a random line between Sec. 14 and 23.</p> <p style="text-align: center;">Va. 20° 30' East.</p>	
40.00	Set post for temporary $\frac{1}{4}$ sec. cor.	
79.22	<p>Intersected N. and S. line, 58 lks. North of cor. to Sec. 13, 14, 23 and 24 from which cor. I run N. 89° 35' West on a true line between Sec. 14 and 23.</p> <p style="text-align: center;">Va. 18° 45' East.</p>	
38.50	Ravine, course South.	
39.61	Set stone, 20x12x4 on East hillside for $\frac{1}{4}$ sec. cor.	+50
79.22	<p>The cor. to Sec. 14, 15, 22 and 23.</p> <p>Land: surface very broken and mountainous. Soil, 3rd rate. No timber; good grass.</p> <p>Sec. 23 has some 1st rate soil on river bottom. Bottom is from 3 to 8 chs. wide and is mostly covered with good timber. All South of river has more or less timber.</p>	
	<p>North between Sec. 14 and 15.</p> <p style="text-align: center;">Va. 20° 30' East.</p>	
40.00	Set stone 20x12x5 on West hillside for $\frac{1}{4}$ sec. cor.	+900
46.00	Enter timber, course E. & W.	
80.00	<p>Set fir post for cor. to Sec. 10, 11, 14 &amp; 15, from which a</p> <p>A fir, 8 in diam. brs. N. 10° E. 70 lks. dist.</p> <p>A fir, 10 in diam. brs. S. 42° E. 40 lks. dist.</p> <p>A fir, 8 in diam. brs. S. 28° W. 27 lks. dist.</p> <p>A fir, 8 in diam. brs. N. 70° W. 22 lks. dist.</p> <p>Land; Surface, mountainous. Soil, 3rd, 2nd and 1st rate. Good timber on N. 30 chs. Pine, fir and tamarack.</p>	+100