

Subdivisional Lines of Township 3 North, Range 36 E. W. M.

Chains	
	<p>Good grass South of timber.</p> <hr/> <p>East on a random line between sections 11 and 14. Va. 21°15' East.</p>
40.00	Set post for temporary $\frac{1}{4}$ sec. cor.
79.10	<p>Intersected N. and S. line 46 lks. North of corner to Sec. 11, 12, 13 and 14, from which cor. I run N.89°40' West on a true line between Sec. 11 and 14. Va. 22° East.</p>
39.55	Set fir post for $\frac{1}{4}$ sec. cor.
	<p>A fir, 4 in diam. brs. N. 40° W. 23 lks. dist. A fir, 16 in diam. brs. S. 48° ". 21 lks. dist.</p>
79.10	<p>The cor. to Sec. 10, 11, 14 and 15. Land: Surface rolling: Soil, 2nd and 1st rate; good tim- ber. Fir, pine and tamarack, willow and some other underbrush. The N. $\frac{1}{2}$ of the N. $\frac{1}{2}$ of Sec. 14 is most- ly covered with good timber. The remainder of the section is steep South hillside with good grass and mostly stony.</p> <p style="text-align: right;">Oct. 7th 1878.</p> <hr/> <p>North between Sections 10 and 11. Va. 21°15' East.</p>
40.00	Set willow post on West hillside for $\frac{1}{4}$ sec. cor. from which
	<p>A fir, 13 in diam. brs. N. 40° E. 12 lks. dist. A tamarack, 15 in diam. brs. S. 10° W. 44 lks. dist.</p>
80.00	Set fir post on South side of brook for corner to sec- tions 2, 3, 10 and 11, from which
	<p>A fir, 12 in diam. brs. N. 78° E. 87 lks. dist. A fir, 11 in diam. brs. S. 24° E. 26 lks. dist. A fir, 16 in diam. brs. S. 50° W. 78 lks. dist. A fir, 18 in diam. brs. N. 52° W. 88 lks. dist.</p> <p>Land: Surface, hilly. Soil, 2nd and 1st rate; Good timber, most of the distance. Scattering in a few places. Tamarack, pine & fir. Willow and some other underbrush.</p>