

Subdivisional Lines of Township 3 North Range 36 E. W. M.

Chains	Down along South side of spur.	
36.30	Set stone 16x10x5 on SW. hillside for $\frac{1}{4}$ sec. cor.	-200
68.00	Brook 30 lks. wide, course North.	-600
72.60	The cor. to Sec. 27, 28, 33 & 34.	+200
	Land: Surface; steep mountain sides; Soil, 3rd rate; Some timber along brook. Fir, tamarack and pine: good grass. Section 34 is very broken and about $\frac{1}{8}$ is covered with timber, in small groves in different places and a narrow belt along the brook.	
	North between Sec. 27 and 28	
	Va. $17^{\circ}30'$ East.	
	Along down East side of ridge.	
38.50	Creek bottom	
40.00	Set stone 18x12x7 in creek bottom for $\frac{1}{4}$ sec. cor. from which	-250
	A fir, 8 in diam. brs. S. 10° E. 30 lks. dist.	
	A fir, 6 in diam. brs. S 46° W. 6 lks. dist.	
52.50	Creek, 26 lks. wide, course N. 10° W.	
80.00	Set stone 18x12x8 on steep West hillside for corner to sections 21, 22, 27 and 28 from which	+100
	A pine, 14 in diam. brs N. 54° E. 21 lks. dist.	
	A pine, 14 in diam. brs. S 87° E. 61 lks. dist.	
	A fir, 18 in diam. brs. S 41° W. 99 lks. dist.	
	A fir, 30 in diam. brs N. 45° W. 80 lks. dist.	
	Land: Surface, mountainous; Soil, 3rd and 2nd rate. Good timber along most of this mile, Fir, pine, tamarack and balm: Willow and some underbrush.	
	Oct. 10th 1878.	
	East on a random line between Sec 22 and 27.	
	Va. $20^{\circ}30'$ East.	
40.00	Set post for temporary $\frac{1}{4}$ sec. cor.	
72.80	Intersected N. and S. line 38 lks. North of corner to sec. 22, 23, 26 and 27, from which corner I run	
	N. $89^{\circ}44'$ West on a true line between Sections 22 and 27	
	Va. $15^{\circ}30'$ East.	
36.40	A fir, 16 in diam. for $\frac{1}{4}$ sec. cor.	+100
	A fir, 16 in diam brs. N. 85° W. 15 lks. dist.	