

Subdivisional Lines of Township 3 North, Range 36 E. W. M.

Chains 30.28	<p>To a point 8.56 lks. S. 20° West of 35th mile post on re-                  servation's line.</p> <p>Set fir post at point of intersection.</p> <p>A pine, 10 in diam. brs. South 12 lks. dist.</p> <p>A fir, 8 in diam. brs. N. 48° E. 64 lks. dist.</p> <p>Land, surface, broken. Soil, 3rd rate. Good timber. Fir,                  pine and tamarack. Some grass. Some willow underbrush.</p> <p style="text-align: center;">Oct. 16th 1878</p>	+250
	<p>West on a true line between Sec. 10 and 15.</p> <p style="text-align: center;">Va. 21° 15' East.</p>	
40.00	<p>Set fir post for <math>\frac{1}{4}</math> sec. cor.</p> <p>A tamarack 13 in diam. brs. N. 2° W. 36 lk. dist.</p> <p>A fir, 20 in diam. brs. S. 51° W. 52 lks. dist.</p>	
51.16	<p>To a point N. 69° W. 150 lks. and N. 44° W. 20 lks. from                  33 mile post on the boundary of U. Indian reservation.</p> <p>Set fir post at point of intersection for cor. to Sec.                  10 and 15, from which</p> <p>A fir, 18 in diam. brs. N. 30° E. 53 lks. dist.</p> <p>A fir, 8 in diam. brs. S. 85° E. 53 lks. dist.</p> <p>Land; Surface, hilly; Soil, 2nd and 1st rate; Good timber.                  Tamarack, fir and pine.</p> <p>I find an error in the above closing. I therefore care-                  fully run an measure from 33 to 34th mile post and                  find the distance 82.50 chs. instead of 80.00 chs. or                  86.00 chs. as given in field notes and 21.8 chs. East                  of 34th mile post.</p> <p style="text-align: center;">Oct. 17, 1878.</p>	+
	<p>West on a true line between sections 3 and 10.</p> <p style="text-align: center;">Va. 21° 15' East.</p>	
7.00	<p>Brook, 6 lks. wide, course SW.</p>	
9.00	<p>Leave timber NE. &amp; SW. open hillside.</p>	
40.00	<p>Set stone 20x10x8 on East hillside for <math>\frac{1}{4}</math> sec. cor. from                  which</p> <p>A pine, 38 in diam. brs. N. 2° E. 126 lks. dist.</p> <p>A pine, 20 in diam. brs. S. 4° E. 77 lks. dist.</p>	