

Subdivisional Lines of Township 3 North, Range 36 E. W. M.

Chains	Land: Surface rolling: Soil, 1st and 2nd rate. Good grass. Good farming land.	
	North on a random line between Sec. 5 and 6 Va. 19° East.	
40.00	Set pot for temporary 1/4 sec. cor.	
75.75	Intersected North Boundary 188 lks. East of cor. to Sec. 5 and 6 from which cor. I run S. 1°21' East on a true line between Sec. 5 and 6. Va. 21° East.	
9.00	Fence and field E. and W.	+100
26.50	Fence, E. and W.	
32.00	Fence, E. and W. leave field.	
35.75	Set stone 20x12x5 for 1/4 sec. cor. A pine, 20 in diam. brs. N. 20° E. 133 lks. dist. a pine, 17 in diam. brs. S. 66° W. 229 lks. dist.	
46.00	House, West of line, 120 lks.	
48.00	Road, E. and W. to timber, also a fence and field E. & W.	
75.75	The cor. to Sec. 5, 6, 7 and 8. Land: Surface, rolling. Soil, 1st and 2nd rate. A few scattering pine trees in N. 1/2 mile. Good grass. Good farming land.	-200
	To show that there has been an error made in the closing of this Township at the NW. cor., I begin at the corner to Sections 5 and 6 on the North boundary and carefully run and measure West, and at 66.75 chs. I intersect West Boundary 8.90 chs. South of corner to Townships 3 and 4 North and Ranges 35 and 36 East, showing plainly that the closing was not made as represented in the field notes.	
	Survey of the Subdivisional Lines of Township 3 North, Range 36 East Willamette Meridian, Oregon, as surveyed by James P. Currin and James Noland, U. S. Deputy Surveyors, under their special contract, dated May 4th 1878	
	Commencing at Meander cor. to fractional sections, 9 and 10, which is a post, 4 ft. long, 4 ins. square, set	