

Subdivisional Lines of Township 3 North, Range 36 E.W. M.

Chains	
	<p>firmly in the ground, marked M C U R on S., S 10 on E., and S 9 on W. faces, from which</p> <p>A fir, 10 ins. diam. bears N. 78° E. 23 lks. dist., marked T 3 N S 10 U R M C B T</p> <p>A fir, 10 ins. diam. bears N. 32° W. 65 lks. dist., marked R 36 E S 9 U R M C B T.</p> <p>Thence South on true line.</p> <p style="text-align: center;">Va. 19° East.</p> <p>15.85 Set basalt stone 12x12x10 ins. 8 ins. in the ground for cor. to Secs. 9, 10, 15 and 16, marked with 4 notches on S. and 3 notches on E. edges, from which</p> <p>A pine, 16 ins. diam. bears N. 53° E. 90 lks. dist., marked T 3 N R 36 E S 10 B T.</p> <p>A pine, 10 ins. diam. bears S. 53° E. 107 lks. dist., marked T 3 N R 36 E S 15 B T</p> <p>A pine, 16 ins. diam. bears S. 43° W. 219 lks. dist., marked T 3 N R 36 E S 16 B T.</p> <p>A pine, 16 ins. diam. bears N. 53° W. 48 lks. dist., marked T 3 N R 36 E S 9 B T.</p> <p>This cor. is in center of wagon road E. and W.</p> <p>Land, rolling. Soil, 2nd rate. Timber; pine and fir with thick undergrowth of same. 15.85 chs.</p>
	<p>East on ran. bet. Secs. 10 &amp; 15.</p> <p style="text-align: center;">Va. 19° East.</p> <p>30.34 A point, 2.13 chains S. of Meander cor. to fractional Secs. 10 and 15, which is a post, 4 ft. long, 4 ins. square, set firmly in the ground, marked U R M C on W. face, S 10 on N. and S 15 on S. faces, from which</p> <p>A fir, 18 ins. diam. bears N. 30° E. 53 lks. dist., marked U R M C T 3 N S 10 B T.</p> <p>A fir, 8 ins. diam. bears S. 85° E. 53 lks. dist., marked U R M C R 36 E S 15 B T. Thence</p> <p>S. 86°00' W. on true line.</p> <p style="text-align: center;">Va. same.</p>
27.00	Wagon road, NE. and SW.

2011  
1585  
1585

1116  
1585  
1585