

Subdivisional Lines of Township 3 North, Range 36 E.W. M.

Chains
30.41

Cor. to Secs. 9, 10, 15 and 16.

Land, rolling. Soil 2nd rate. Timber: pine and fir and dense undergrowth of same. 30.34 chains.

Beginning at meander cor. to fractional Secs. 8 and 9, which is a post, 4 ft. long, 4 ins. square, 24 ins. in the ground, marked U R M C on S. face, from which

A fir, 14 ins. diam. bears N. 40° E. 48 lks. dist. marked U R M C T 3 N S 9 B T.

A fir, 10 ins. diam. bears N. 77° W. 46 lks. dist. marked U R M C R 36 E S 8 B T.

I run

South on true line bet. Secs. 8 and 9.

Va. 20° East.

11.89

Set post 3 ft. long, 3 ins. square, 24 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ S on W. face, from which

A tamarack, 8 ins. diam. brs S 60° E. 12 lks. dist. marked $\frac{1}{4}$ S B T.

A tamarack, 8 ins. diam. bears West 44 lks. dist., marked $\frac{1}{4}$ S B T.

25.29

Gulch course N. W.

-20

29.64

Wagon Road N.W.

51.89

Set post 4 ft. long, 4 ins. square, 24 ins. in the ground for cor. to Secs. 8, 9, 16 and 17, marked T 3 N S 9 on

N. E. R 36 E S 16 on SE. S 17 on SW., and S 8 on NW.

faces with 4 notches on S. and E. edges, from which

A tamarack, 5 ins. diam. bears N. 65° E. 7 lks. dist. marked T 3 N R 36 E S 9 B T.

A fir, 18 ins. diam. bears S 40° E. 60 lks. dist., marked T 3 N R 36 E S 16 B T.

A tamarack, 4 ins. diam. bears S. 70° W. 33 lks. dist. marked T 3 N R 36 E S 17 B T.

A fir, 5 ins. diam. bears N. 30° W. 10 lks. dist. marked T 3 N R 36 S 8 B T.

Land rolling. Soil, 2nd rate. Covered with fir, pine and dense undergrowth. 51.89 chs.