

Subdivisional Lines of Township 3 North, Range 36 E. W. M.

Chains 21.21	<p>A point, 109 lks. S. of Closing cor., set by Deputy Surveyor Pershin, which is a stone, 14x12x10 ins. set firmly in the ground, marked U R C C and mound of stone around it. Thence</p> <p>S. 87°04' W. on true line.</p> <p style="text-align: right;">Va. same.</p> <p>Descend.</p>	
21.21	<p>Cor. to Secs. 28, 29, 32 and 33.</p> <p>Land, steep mountainside.</p> <p>Grass, good. 21.21 chs.</p> <p>Soil, 4th rate and rocky.</p>	
North bet. Secs. 28 and 29.		
Va. 20° East		
6.50	Summit of ridge, W.	+250
19.85	Cañon, W.	-250
31.50	Summit ridge, W.	+250
40.00	<p>Set post 4 ft. long, 4 ins. square, 24 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ S on W. face, from which</p> <p>A pine, 14 ins. diam. bears N. 20° E. 165 lks. dist., marked $\frac{1}{4}$ S B T.</p> <p>A pine, 18 ins. diam. bears N. 30° W. 200 lks. dist., marked $\frac{1}{4}$ S B T.</p>	
64.50	Umatilla river 100 lks. runs SW.	-600
67.50	Wagon road, SW.	
70.25	<p>Spring branch, 10 lks. wide S. 10° E.</p> <p>Ascend.</p>	
80.00	<p>Set basalt stone 10x8x6 ins., 6 ins. in the ground for cor. to Secs. 20, 21, 28 and 29, marked with 2 notches on S. and 4 notches on E. edges, and raised mound of stone over it.</p> <p style="text-align: right;">80.00 chs.</p> <p>Land, mountainous S. of river. Soil, 3rd rate. Timber: pine and fir on N. sides of hills and along river.</p> <p>Grass, poor.</p>	+600
East on ran. bet. Secs. 21 and 28.		
Va. 21° East.		