

## Subdivisional Lines of Township 3 North, Range 36 E. W. M.

Chains	and S. of post, $5\frac{1}{2}$ ft. dist., and raised mound of earth, $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it. marked post $\frac{1}{4}$ S. on W. face. Canon, SE.	-100
47.00		
53.50	Summit of ridge, SE.	+200
80.00	Set basalt stone 12x10x6 ins., 8 ins. in the ground for cor. to Secs. 16, 17, 20 and 21, and raised mound of stone over it. Land, mountainous. 80 chs, Soil, 4th rate and rocky. Good bunch grass.	+15
East on ran. bet. Secs. 16 and 21. Va. 20° East.		
40.00	Set temporary $\frac{1}{4}$ sec. cor. and at	
82.01	A point, 44 lks. S. of cor. to Secs. 15, 16, 21 and 22., which is a stone 14x10x8 ins. on E. side of ridge with mound of stone around it. Thence S 89° 41' W. on true line. Va. 21° East.	+300
2.79	Closing cor. set by Pershin, which is a stone 15x12x10 ins. set firmly in the ground, marked with (x) on top and mound of stone around it.	
12.22	Canon, SW.	-300
26.22	Summit of ridge.	+100
41.00	Set basalt stone 16x16x8 ins. 10 ins. in the ground for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face., and raised mound of stone over it.	
42.00	Canyon, S.	-200
54.20	Road on Summit, S.	+180
63.20	Canyon SE.	-200
79.20	Summit of ridge.	
82:01	Cor. to Secs. 16, 17, 20 and 21. Land, rough & mountainous. 79.22 chs. Soil, 3rd rate. Good bunch grass.	