

Subdivisional Lines of Township 3 North, Range 36 E. W. M.

Chains	<p>From the closing cor. on U. R. bdy. between Secs. 15 and 16, 8.04 chs. North of cor. to Secs. 15, 16, 21 &amp; 22 which is a stone 18x12x5 ins. set in stone mound I run North on random bet. Secs. 15 &amp; 16.</p> <p style="text-align: right;">Va. 21° E.</p>	
31.96	Set temporary $\frac{1}{4}$ sec. corner.	
68.94	Intersect 10.46 chs. E. of corner to Secs. 9, 10, 15 and 16. Thence S. 8° 40' E. on true line between Secs. 15 & 16.	
	Va. 19° E.	
12.18	Canyon, SW.	-150
30.34	Summit of ridge.	+150
37.41	Set basalt stone 12x10x10 ins. 8 ins. in the ground for $\frac{1}{4}$ sec. corner, marked $\frac{1}{4}$ on W. face, and raised mound of stone over it.	-90
46.53	Canyon, SW.	-150
60.74	Summit of ridge, W.	+200
69.74	To U R closing corner.	
	Land, mountainous. 69.74 chs.	
	Soil, 3rd rate. Some timber in canyon.	
	Sept. 14th 1887.	
	North on random bet. Secs. 16 & 17.	
	Va. 20° East.	
40.00	Set temporary $\frac{1}{4}$ sec. corner.	
79.00	Intersect E. & W. line 8.57 chains East of corner to Secs. 8, 9, 16 & 17. Thence S. 6° 12' E. on true line.	
	Var. 19° East.	
11.32	Wagon road, E. & W.	
39.23	Set post 4 ft. long, 4 ins. square, 24 ins. in the ground for $\frac{1}{4}$ sec. corner, marked $\frac{1}{4}$ S on W. face. Dug pits 18x18x12 ins. N. and S. of post, 5 $\frac{1}{2}$ ft. dist. and raised mound of earth, 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it.	
50.30	Leave timber and descend.	