

Subdivisional Lines of Township 3 North, Range 36 E. W. M.

<p>Chains 56.85 79.60</p>	<p>Same river, SW. 80 lks. wide. The cor. to Secs. 29, 30, 31 & 32. Land, mostly along bank of river. Heavy underbrush, some pine and balm timber. 79.60 chs. Soil, rocky 4th rate. Sept. 13th 1887.</p>	
<p>17.50 21.00 40.00 70.00 80.00</p>	<p>North bet. Secs. 29 and 30. Va. 20$\frac{1}{2}$° East. Umatilla river, 100 lks. wide, W. Ascend steep mountain side. Set basalt stone 9x8x7 ins. 6 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on West face, and raised mound of stone over it. Gradually ascend steep side of ridge. Top of ridge. Set post 4 ft. long, 4 ins. square, 24 ins. in the ground for cor. to Secs. 19, 20, 29 and 30, marked, T 3 N S 20 on NE., R 36 E S 29 on SE., S 30 on SW. and S 19 on NW. faces with 2 notches on S. and 5 notches on E. edges, from which A fir, 8 ins. diam. bears N. 40° E. 85 lks. dist., marked T 3 N R 36 E S 20 B T. A pine, 36 ins. diam. bears S. 47° E. 10 lks. dist., marked T 3 N R 36 E S 29 B T. A pine, 30 ins. diam. bears S. 80° W. 90 lks., marked T 3 N R 36 E S 30 B T. A pine, 18 ins. diam. bears N. 55° W. 66 lks. dist., marked T 3 N R 36 E S 19 B T. Land, broken & mountainous. 80 chs. Soil, 2nd rate. Timber along river bottom.</p>	<p>+600</p>
<p>40.00 80.00</p>	<p>East on ran. bet. Secs. 20 and 29. Va. 19° East. Set temporary $\frac{1}{4}$ sec. cor. Intersect N. & S. line 10 lks. S. of cor. to Secs. 20,</p>	