

Subdivisional Lines of Township 3 North, Range 36 E. W. M.

Chains	<p>$\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on N. face, and raised mound of stone, $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.</p>	
44.00	Summit, hill & enter timber.	+75
79.80	Cor. to Secs. 17, 18, 19 and 20. Land, mountainous. 79.80 chs. Soil, 2nd rate & rocky. Scattering pines on last $\frac{1}{2}$ mile	
	West on ran. bet. Secs. 18 and 19.	
40.00	Set temporary $\frac{1}{4}$ sec. cor. and at	
79.25	Intersect W. bdy. Township 75 lks. S. of cor. to Secs. 18, 19, 13 and 24. Thence S.89°28' E. on true line. Va. 22 $\frac{1}{2}$ ° East.	
39.25	Set basalt stone 12x10x8 ins. 8 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ S on N. face, and raised mound of stone, $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.	
58.20	Wagon road, course NE.	
64.00	Gulch, course SW.	-15
79.25	Cor. to Secs. 17, 18, 19 and 20. Land, high and rolling. Soil, 1st rate and fine bunch grass. Scattering timber, pine & fir.	
	North on ran. bet. Secs. 17 and 18. Va. 22 $\frac{1}{2}$ ° East.	
40.00	Set temporary $\frac{1}{4}$ sec. cor. and at	
49.72	A point 9.00 chains E. of meander cor. to Secs. 17 & 18, which is an old post rotted down, and as the exact lo- cality of this cor. can only be ascertained in one way, I go to cor. to Secs. 7, 8, 17 & 18, which is a post from which A pine, 30 ins. diam. bears N. 45° E. 5 lks. dist. A pine, 24 ins. diam. bears S. 36° W. 12 lks. dist. Marks are illegible. I run South on true line bet Secs. 17 and 18. Va. 21° East.	
27.71	Set old post 24 ins. in the ground, and also a stone	