

Subdivision of Township 3 North 36 East

Chains

Land, rolling.

Scattering timber.

Good grass.

June, 7th 1889

From the corner to Secs. 13, 18, 19 and 24, on the West
bdy. of Township.

I run

South on true line between Secs. 19 and 24.

Var. 18°45'E.

10.00

Set post 3 ft. long 3 ins. square with charred stake 12
ins. in the ground, for 1/32 Sec. corner marked 1/32 S
on W. face, dug pits 18x18x12 ins. N. & S. of post
5½ ft. dist. and raised a mound of earth 1½ ft. high
3½ ft. base around post.

20.00

Set post 3 ft. long 3 ins. square with marked stone 12
ins. in the ground for 1/16 & 1/32 Sec. corner marked
1/32 S. on N. face & 1/16 on S. face, dug pits 18x18x12
ins., N. & S. of post 5½ ft. dist. and raised mound of
earth 1½ ft. high 3½ ft. base around post.

30.00

Set basalt stone 12x10x4 ins. 8 ins. in the ground for
1/32 Sec. corner marked 1/32 on W. face, dug pits 18x18
x12 ins. N. & S. of stone 5½ ft. dist. and raised mound
of earth 1½ ft. high 3½ ft. base over it.

40.00

Line through timber.

40.00

Intersect the ¼ Sec. corner which is a basalt stone 12x
10x8 ins. 8 ins. in the ground, marked ¼ on W. face,
dug pits 18x18x12 ins. N. & S. of stone 5½ ft. dist.
and mound of earth 1½ ft. high 3½ ft. base alongside.

Over mound summit N. & S.

50.00

Set basalt stone 9x8x7 ins. 6 ins. in the ground for 1/32
Sec. corner marked 1/32 on W. face, dug pits 18x18x12
ins. N. & S. of stone 5½ ft. dist. and raised mound of
earth 1½ ft. high 3½ ft. base over it.

52.50

Gulch course W.