

Township 3 N., R. 37 E., W.M.

Chains	A Tamarack, 14 ins. in diam., bears S. 42°E., 16 lks.	
57.50	On Bluff, course E.&W.	+ 100
72.00	Brook, 12 lks. wide, course W.	-600
73.00	Leave timber, E.&W.	
80.00	Set Basalt Stone, 18 x 12 x 4, on steep S. hillside for Cor. Secs. 24, 25, 19 & 30.	+200
	A Pine, 18 ins. in diam., bears N. 84° W., 49 Lks.	
	A Fir, 12 " " " " N. 54° E., 63 "	
	No other trees.	
	Land; surface mountainous; soil 3rd rate; good timber in places, but mostly scattering Fir, Tamarack and Pine.	
	April 17, 1879.	
North on E. Bdy. of Sec. 24		
	Var. 18° 30' E.	
13.00	On Ridge and enter timber, E.&W.	+500
40.00	Set Fir post on N.E. mountain side for $\frac{1}{4}$ Sec. Cor. A Tamarack, 28 ins. in diam., bears E. 9 lks. distant A Fir, 5 " " " " N. 40°W. 17 lks.	
72.00	North branch of Umatilla River, course W.	+1200
73.00	Leave timber, course E.&W.	
80.00	Set Basalt Stone, 14 x 10 x 8 on steep S. mountain side Drove Stake and raised Mound of stone around Stone and Stake in lieu of pits for Cor. to Secs. 13, 24, 18 & 19 Land; surface steep mountain side; soil, 3rd rate and rocky. Some good timber, Fir, Tamarack & Pine.	+350
North on E. Bdy. of Sec. 13		
	Var. 23° 00' E.	
25.00	On Spur, extending W. and enter timber.	+600
36.00	Ravine opens W.	-300
40.00	Set Basalt Stone, 14 x 10 x 5 on S.W. face of Spur for $\frac{1}{4}$ Sec. Cor.	+100
56.00	On Spur and enter timber E.&W.	+300
69.75	Brook 10 lks. wide, course N.W.	-400
80.00	Set Basalt Stone, 14 x 12 x 5 on W. face of mountain for Cor. to Secs. 12, 13, 7 & 18	+200