

Township No. 3 North Range No. 37E, Willamette Meridian.

Chains

80.00 Set fir post 6 ins. square, 6 ft. long on nearly level for  
Corner to Townships 3 & 4 North, Ranges 37 & 38 East, W.M.

A Fir, 38 ins. in diam., bears N.58° E. 55 Lks. dist.

" " 24 " " " " S.76° E. 110 " "

" " 30 " " " " S.33° W. 93 " "

" " 32 " " " " N.45° W. 74 " "

Land; surface, North 70 chains nearly level. Soil, 3rd &  
2nd rate. Heavy timber, Fir, Tamarack, Spruce and Pine.  
Some willow and alder underbrush

April 23, 1879

From the Corner to Townships 3 & 4 North, Ranges 37 & 38 E

I run

West on a random line along the North boundaries of Secs.  
1, 2, 3 & 4.

Var. 20° 00' East

At 4 miles, 2 chains and 58 Lks. to a point 113 Lks. N. of  
the Corner to Secs. 32, 33, 4 & 5, I find the post standing  
and the witness trees as described by the field notes  
furnished by the office.

My connection will therefore be 28 Lks. S. per mile. I  
therefore begin at the corner to Secs. 4, 5, 32 & 33 on the  
N. Boundary of the Township and I run a true line N. 89°  
48' East on the North Boundary of Sec. 4.

Var. 19° 30' East

42.58 Set a fir post on level for  $\frac{1}{2}$  Sec. Corner; from which a  
Tamarack, 22 ins. in diam., bears N.30° E. 10 Lks. dist.

Fir 6 " " " " S.65° W. 11 " "

82.58 Set fir post on level for Corner to Secs. 3, 4, 33 & 34;  
from which

A Tamarack, 12 ins. in diam., bears N.34° E. 54 Lks.

" " 11 " " " " S.46° E. 20 "

" Fir 18 " " " " S.52° W. 43 "

" Tamarack 14 " " " " N.62° W. 31 "

Land; surface nearly level. Timber, Tamarack, Fir, Spruce &  
Pine.  
Soil: 2nd grade.