

Township 3 N., R. 37 E., W.M.

Chains		
	<p>A Fir, 8 ins. in diam., bears S. 35°E., 73 lks. dist. " " 7 " " " " S. 36°W. 45 " " " " 6 " " " " N. 72°W., 55 " "</p> <p>No other trees near.</p> <p>Land; surface, mountainous. Soil; 3rd rate. Timber on W. 72 chains. In places large and heavy and in other places dense young timber. Fir, Pine, Tamarack, etc.</p>	
	<p>S. 89°45' W. on a true line along S. Boundary of Sec. 14. Var. 11° 30' E.</p>	
	<p>Along irregular N. face of Bluff.</p>	
40.18	<p>Set Fir post on N. face of Bluff for $\frac{1}{4}$ Sec. Cor. A Bar Birch, 18 ins. in diam., bears N. 18° W., 28 lks. dist. A Fir, 4 " " " " S. 78° E., 37 " "</p>	
51.00	<p>Foot of Bluff, course N.E. & S.W.</p>	+500
55.00	<p>Q. point of Spur</p>	+80
63.00	<p>Umatilla River, course S.W.</p>	-80
80.35	<p>Set Basalt Stone 18 x 14 x 12 on steep S.W. face of Bluff for Cor. to Secs. 14, 15, 22, & 23. A Fir, 30 ins. in diam., bears N. 66° W., 146 lks. dist. A Pine, 14 " " " " S. 66° E., 147 " "</p> <p>No other trees near.</p> <p>Land; surface, mountainous. Soil 3rd rate. Heavy timber except W. 15 chains scattering. Pine, Fir and Tamarack.</p> <p>Oct. 16, 1879.</p>	+60
	<p>S 89° 45' W. on a true line along the South Boundary of Sec. 15. Var. 24°00' E.</p>	
	<p>Up along irregular S. face of bluff.</p>	
40.18	<p>Set Basalt Stone 18 x 12 x 7 on steep S. face of Bluff for $\frac{1}{4}$ Sec. Cor. No trees near.</p>	+400
75.00	<p>Enter scattering timber</p>	
80.35	<p>Set Basalt Stone 18 x 8 x 6 on S. face of Bluff for Cor. to Sec. 15, 16, 21 & 22. A Pine, 30 ins. in diam., bears N. 64° E., 184 lks. dist.</p>	-300