

Chains	Good bunch grass in open ground.	Oct.17,1879.
North between Secs. 13 & 14.		
Var. 11° 30' E.		
Steep descent.		
14.00	Foot of Bluff.	-400
16.50	North for Umatilla River, 40 lks. wide, course W.	
31.00	Leave heavy timber.	
40.00	Set basalt Stone 14 x 10 x 5 on E. side of Spur for ¼ Sec Cor. No trees near.	
80.00	Set Pine post 4 ins. sq. and 4 ft. long in mound of stone on S. side of mountain for Cor. to Secs. 11, 12, 13 & 14 Land; surface mountainous. Soil; 3rd rate. Heavy timber on S. 30 chains. On N. 50 chains, scattering and open glades. Fir, Pine & Tamarack. Good grass in open ground.	+1000
East on a random line between Secs. 12 & 13.		
Var. 22° 00' E.		
40.00	Set post for temporary ¼ Sec. Cor.	
80.22	Intersected E.Bdy. 92 lks. S. of Cor. to Sec.12 & 13 from which Cor. I run S.89°21' W. on a true line between Sec. 12 & 13.	
Var. 18° 30' E.		
31.50	Brook, 18 lks. wide, course S.	-450
40.11	Set Basalt Stone 18 x 12 x 4 on steep E.Face of Spur for ¼ Sec. Cor.	
A Fir, 6 ins. in diam., bears N. 28°W. ,54 Lks. dist " " 11 " " " " S. 98 " "		
75.50	On Ridge, course N.W.& S.E. & leave timber	+900
80.22	The Cor. to Secs.11, 12, 13 & 14.	-50
Land; surface mountainous. Soil; 3rd rate. Heavy timber, with open glades. Fir, Pine & Tamarack. Bunch grass in glades.		
Oct. 18, 1879.		