

Township 3 N., R. 37 E., W.M.

Chains	North between Secs. 11 & 12.	
		Var. 22° 00' E.
4.00	On Ridge, course N.W. & S.E. along irregular N.E. face of Bluff.	+50
40.00	Set Basalt Stone 16 x 10 x 6 on N.E. face of Bluff for $\frac{1}{4}$ Sec. Cor.	
	A Fir, 5 ins. in diam., bears W. 10 lks. dist.	
	" " 6 " " " " S. 30° E. 26 Lks. dist.	
80.00	Set Basalt Stone 16 x 14 x 4 on steep N.E. face of Bluff for Cor. to Secs. 1, 2, 11 & 12.	+400
	A Fir, 10 ins. in diam., bears N. 15° E. 70 lks. dist.	
	" " 12 " " " " S. 46° E. 24 " " "	
	" " 11 " " " " S. 38 °W. 15 " " "	
	" " 16 " " " " N. 40°W. 34 " " "	
	Land; Surface, mountainous. Soil; 3rd rate, heavy timber and open glades about $\frac{1}{2}$ of each. Fir, Pine & Tamarack. Good grass in open glades.	
	East on a random line between Sec. 1 & 12.	
		Var. 19° 45' E.
40.00	Set post for temporary $\frac{1}{4}$ Sec. Cor.	
80.04	Intersected E. Boundary 68 lks. S. of Cor. to Secs. 1 & 12 from which Cor.	
	I run	
	S. 89° 31' W. on a true line between Secs. 1 & 12.	
		Var. 19° 15' E.
40.02	Set Fir post on level plateau for $\frac{1}{4}$ Sec. Cor.	+ 200
	A Fir, 12 ins. in diam., bears N. 80° E., 25 lks. dist.	
	" " 11 " " " " S. 35° E., 11 " " "	
74.50	Brook, 16 lks. wide, course S.E.	-500
80.04	The Cor. to Secs. 1, 2, 11 & 12.	+100
	Land; surface mountainous. Soil, 3rd rate. Heavy timber nearly all along this mile, Fir, Pine & Tamarack.	
	North on a random line between Secs. 1 & 2.	
		Var. 19° 45' E.