

Township 3 N., R. 37 E., W.M.

Chain		
40.00	Set post for temporary $\frac{1}{4}$ Sec. Cor.	
80.22	Intersected N.Bdy. at Cor. to Secs. 1 & 2 from which Cor. I run S. on a true line between Sec. 1 & 2. Var. 20° 30' E.	
11.50	Spring branch, course S.W.	
40.22	Set Fir post on S.W. slope for $\frac{1}{4}$ Sec. Cor. A Fir, 12 ins. in diam., bears N. 17° E., 27 lks. dist. " " 12 " " " " N. 50 °W., 6 "	
69.00	Brook, 10 lks. wide from N.W. to S.	
73.50	Brook, " " " " N. to S.E.	500
80.22	The Cor. to Secs. 1, 2, 11 & 12. Land; surface, mountainous. Soil, 3rd rate. Heavy timber, Fir, Tamarack & Pine & Spruce. Oct. 20, 1879	80
	North between Secs. 14 & 15. Var. 24° 00' E.	
40.00	Set Basalt Stone 14 x 10 x 5 on steep E. side of Spur for $\frac{1}{4}$ Sec. Cor. A Fir, 4 ins. in diam., bears N. 50°W., 24 lks. dist. " " 10 " " " " S. 15°E., 97 " "	
80.00	Set Tamarack post, 4 ins. sq., 4 ft. long in mound of stone stone on steep rocky S. face of Bluff for Cor. to Secs. 10, 11, 14 & 15. No trees. Land; surface mountainous. Soil 3rd rate. Only a few small groves of timber. Mostly open mountain side. Good grass.	900
	East on a random line between Secs. 11 & 14. Var. 21° 30' E.	
40.00	Set post for temporary $\frac{1}{4}$ Sec. Cor.	
80.38	Intersected N. & S. line 76 lks. S. of Cor. to Secs. 11, 12 13 & 14 from which Cor. I run S. 89° 27' W. on a true line between Secs. 11 & 14	