

Chains		
		Var. 22° 00' E.
40.19	A Fir, 18 ins. in diam. in small grove in deep Gulch for ¼ Sec. Cor. A Fir, 12 ins. in diam., bears N. 40°W., 7 lks. dist. A Fir, 14 " " " " S. 5°W. 30 " "	-300
80.38	The Cor. to Secs. 10, 11, 14 & 15 Land; surface mountainous. Soil, 3rd rate. Only few small grove of timber, Fir & Pine. Good bunch grass.	+450
North between Secs. 10 & 11.		
		Var. 21° 30' E.
99.50	Enter heavy timber, course E.& W. , also on table land.	+150
440.00	Set Basalt Stone 14 x 8 x 5 on N.W. slope for ¼ Sec. Cor. A Fir, 10 ins. in diam., bears N. 12° W., 46 Lks. dist. " " 10 " " " " S. 52° E., 47 " "	
68.00	Spring branch, course N.W.	
80.00	Set Fir post on slight W. slope for Cor. to Secs. 2, 3, 10 & 11. A Tamarack, 24 ins. in diam., bears S. 41°W. 73 lks. " " 20 " " " " N. 3°W. 118 "	-100
	No other green trees near, all dead. Land; surface, rolling plateau. Soil; 3rd & 2nd rate. Heavy timber, Fir Tamarack, Spruce & Pine. Some willow and alder underbrush.	
		Oct. 21, 1879.
	East on a random line between Secs. 2 & 11.	
		Var. 22° 00' E.
40.00	Set post for temporary ¼ Sec. Cor.	
80.18	Intersected N.& S. line 84 lks. S. of Cor. to Secs. 1, 2, 11 & 12, from which Cor. I run S. 89° 24' W. on a true line between Secs. 2 & 11.	
		Var. 19° 45' E.
18.00	On Plateau.	
40.09	Set Fir post on level for ¼ Sec. Cor. A Fir, 14 ins. in diam., bears N. 48° W., 48 Lks. dist.	+ 500