

Chains

Sec. Cor.

E. Bdy. of Sec. 25, marked $\frac{1}{4}$ on W. face, from which,
A Pine, 11 ins. in diam., bears S. $66\frac{1}{4}^{\circ}$ W., 23 lks. dist
marked $\frac{1}{4}$ Sec. 25, B.T.

The old $\frac{1}{4}$ Sec. Cor., a Basalt Stone, 12 x 10 x 8 ins.,
marked and witnessed as described by the Surveyor-Gen-
eral, bears S. 4° W., 1 ch., 26 lks. dist.

I destroy all traces of this old $\frac{1}{4}$ Sec. Cor.

Thence along westerly slope; heavy timber; dense under-
growth and fallen poles.

42.50 Steep slope N.W.

47.50 Head of steep Ravine-N. 70° W.; ascend.

55.00 Top of rise; descend into Burk Creek canyon, bears N.E. &
S.W.

60.75 Bluffs, bears N. 60° E. and S. 60° W.

70.20 Foot, -trail, scattered.

70.35 Burk Creek, 10 lks. wide, runs S. 60° W.

70.45 Ascend steep, bluff hill; bears N.E. & S.W.

72.50 Widely scattering timber and heavy growth of bunch grass

80.00 A point 400 ft. below the $\frac{1}{4}$ Sec. Cor. and set an iron-
stone, 20 x 12 x 3 ins., 15 ins. in the ground, for Cor.
of Secs. 24 & 25, marked with 4 notches on N. and 2
notches on S. edges, from which

A Fir, 24 ins. in diam., bears S. 86° W., 1 ch. 45 lks.
marked T. 3 N., R. 37 E., S. 25, B.T.

A Pine, 7 ins. in diam., bears N. 86° W., 3 ch. 72 lks.
dist., marked T. 3 N., R. 37 E., S. 24, B.T.

Note: It was necessary to mark this wit. tree above the
limit prescribed by the Manual; and its use, beyond
the dist. limit, is deemed advisable because of the
fact that both mound of stone, or earth and pits are
impracticable.

The old Cor. of Secs. 24 & 25, a Basalt Stone, 18 x 12
x 4 ins., marked and witnessed as described by the
Surveyor-General, bears S. 4° E., 2 chs. 20 lks. dist.