

## Township 3 N., R. 37 E., W.M.

Chains	<p>I destroy all traces of the old Sec. Cor.  Land, mountainous.  Soil, small part arable, gravelly loam and stones; 2nd &amp; 3rd rates.  Timber, pine, fir, tamarack, alder and spruce.  Undergrowth, fir, pine, tamarack, alder, willow, huckleberry, yew, cascara, thimble berry, fern and bunchgrass  Good pasturage.  Mountainous land, 80.00 chs.    July 26, 1900.</p>
9.75	<p>At 8 A.M., I set off 45° 43' on the lat. arc; 19° 15' on the decl. arc; and determine a true meridian by the solar at the Cor. of Secs. 24 &amp; 25.  Thence I run  N. 0° 56' E., between Secs. 24 &amp; 30.  Ascending steep, bluffy hill; bears E. &amp; W. irregularly.  The closing Cor. of Secs. 19 &amp; 30.</p>
11.00	<p>Thence I run  N. 0° 22' W., between Secs. 19 &amp; 24.  Top of narrow, rock-ridge-divide, between N. fork of Umatilla River and Burk Creek; bears E. &amp; W.; descend.</p>
11.25	<p>Trail from Toll road to Pendleton; bears E. and W.</p>
11.50	<p>Steep descent through dense undergrowth.</p>
11.75	<p>Enter heavy timber; bears E. &amp; W.</p>
17.50	<p>Head of Ravine-N.E.; thence hill bears N. 30° W. and S. 30° E.</p>
26.75	<p>Rill, 1 lk. wide, runs N.E.</p>
31.00	<p>Point, N.E.; thence through dense undergrowth, partially deadened timber and fallen poles of old burn.</p>
37.80	<p>Again make search and fail to find any trace of the old <math>\frac{1}{4}</math> Sec. Cor., E. Bdy. Sec. 24, described by the Surveyor General as a Fir post on N.E. side of mountain, from which,  A Tamarack, 28 ins. in diam., bears E. 9 lks. dist.  A Fir, 5 ins. in diam., bore N. 40° W., 17 lks. dist.</p>
38.25	<p>A Rill, 1 lk. wide, runs N.E.</p>