

Chains 40.00	A point 300 ft. below the Sec. Cor. and set a Basalt Stone, 12 x 10 x 9 ins., 8 ins. in ground, for $\frac{1}{4}$ Sec. Cor., E. Bdy. of Sec. 24, marked $\frac{1}{4}$ on W. face, from which, A Fir, 8 ins. diam., bears S.39°W., 1 ch. 12 lks. dist. marked $\frac{1}{4}$ S.24, B.T.
48.00	Leave dense undergrowth and old burn; thence thru scattering timber.
51.00	Point-N.E.; descend steep N. slope thru small timber and fallen poles.
62.50	Ravine; course N.30°E.
70.00	Foot of mountain; cross narrow, densely overgrown bottom.
71.00	N. Fork of Umatilla River, 25 lks. wide, flows S.70°W.
71.25	Ascends steep, stony hill; bears N.80°E. and S.80°W.
72.50	Leave timber and undergrowth; bears E. & W.
78.00	A point 300 ft. below the $\frac{1}{4}$ Sec. Cor. and the Cor. of Secs. 13 & 24, a Basalt Stone, 14 x 10 x 8 ins., on steep S. mountain side, with Stake and Mound of stone around Stake. The marks thereon changed to indicate Cor. of two Secs. only, as directed by the Manual.  Land; mountainous.  Soil; gravelly and stony; 3rd & 4th rates.  Timber; inferior pine, fir and tamarack.  Undergrowth, pine, fir, tamarack, alder, laurel, willow, huckleberry, pinegrass, alder, fern, thimbleberry and bunchgrass. Good pasturage.  Mountainous land, 78.00 chs.      July 27, 1900.
<b>Resurvey of the S. Bdy. of T.3 N., R.37 E., W.M. As surveyed by same surveyor, under same Contract and date.</b>	
Preliminary to commencing the subdivisions of this Tp., I run W. on S. Bdy. of Sec. 36; at 40.00 chs., fail to find any trace of the $\frac{1}{4}$ Sec. Cor.; set temporary $\frac{1}{4}$ Sec. Cor.; and at 80.00 chs. intersect Cor. of Secs. 35 & 36; therefore, in accordance with my special written instructions and the Manual, after retracement and resurvey of E. Bdy., I resurvey this S. Bdy. of Sec. 36 as follows:	