

Township 3 N., R.37 E., W.M.

Chains	
3.10	Foot; branch of Buck Creek, 8 lks. wide, runs N.85°W., ascend steep hill, bears N.W.& S.E.
14.25	Steep, heavily timbered slope N.
17.50	Shallow Ravine, course N.10°E., thence hill bears N.W. and S.E.
25.00	Top of rise on Ridge, N. of bald point; descend; bears N.E.& S.W.
29.25	Down steep bank.
30.60	Rill, 1 lk.wide, runs N.10°W., thence over point.
32.50	Top of rise and descend.
34.75	Foot; rill, 1 lk.wide, runs N.30° E., ascend steep, grassy hill thru scattering timber and patches of dense undergrowth; bears N.20° E. and S.20° W.
40.00	A point 500 ft. above the Sec. Cor. and set a Basalt Stone 15 x 10 x 4 ins., 10 ins. in ground, for $\frac{1}{4}$ Sec. Cor., S. Bdy. Sec.35, marked $\frac{1}{4}$ on N. face, from which; A fir, 18 ins. diam., bears N.20°E, 96 lks. dist., marked $\frac{1}{4}$ S.35, B.T. The old $\frac{1}{4}$ Sec. Cor.-post missing- bears N.75° W., 1 ch. 10 lks. dist. as determined by witness tree, a fir, 12 ins. diam., marked and witnessed as described by the Surveyor-General I destroy all traces of this old $\frac{1}{4}$ Sec. Cor.
49.00	Top of narrow ridge-point, N.30°E., descend thru heavy timber and undergrowth; bears N.E.& S.W.
54.75	Ascend; bears N.W.& S.E.
57.50	Leave timber and undergrowth; bears N.W.& S.E.
59.75	Top of N.E. brow of mountain; thence gradual ascent thru scattering timber and undergrowth.
70.00	Descend gradually from summit of divide.
78.25	Buck Mt. Trail; bears N.60° W. and S, 60 ° E.